

Impact Outdoors Phase 1 AML Pilot Project
Clay County
Project Description

The proposed Impact Outdoors Phase 1 AML Pilot Project, approximately 30.2 acres total, consists of light gradework and installation of drainage controls to facilitate the development of a recreational campground in Manchester, Clay County. The site is located in the Manchester Quadrangle. The site is at 37° 9' 8.4" N, 83° 47' 15" W. To reach the all the sites from Hal Rogers parkway at KY 80 (Manchester) turn off onto KY 80 north. Go to the stoplight and turn left onto KY 2076. Go 0.9 miles and turn left onto KY 687. Go 0.6 miles and turn left onto Stone Coal Rd and immediately turn right onto the sites gravel access road.

The work will install drainage improvements including culverts, headwalls, erosion control blanket and rock lined ditches. The main site will be lightly graded to drain to the drainage structures. This will allow the next phase, an architecture/engineering design project, to make maximum use of the site. The site has no waste area.

The project site has previously been disturbed by coal mining operations, commercial development, utility installation, road construction, and/or landowner activities. These disturbances consist of significant upheaval, mixing, and removal of earthen material from deep excavation, grading, sub-surface drilling, fill material placement, and erosion. There should be no undisturbed earthen material to a depth of several feet at the areas slated for significant project-related construction activities.

Construction disturbances will be kept to a minimum with a stringently formulated sediment and erosion control program. Prior to beginning any major earth disturbance (excluding initial site preparation for access only), all silt control measures will be installed. These include silt traps and silt barriers (bales & silt fence) at the project site and the waste area. Trees greater than 3" diameter at breast height will be cut in designated areas. All disturbed areas will be promptly revegetated at the end of construction using lime, fertilizer, residential or wildlife seed, and mulch, as necessary. Standard measures will be used for dust control and work hours will occur during AML's standard time frame of 7 am to 7 pm Monday-Friday with shorter hours for "critical" work items. Access to the site is via state highways and existing landowner controlled private roads.